## iMQ

## SQ7101/SQ7103 **Brief Datasheet V2.3**

Page: 1/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

No. : TDDS01-S7101-EN(B)

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

## SQ7101/SQ7103, Secure ASIC, AES-128/AES-256, SHA-256, TRNG

- **Basic Information** 
  - Operating Voltage : 2.0V ~ 5.5V
  - Operating Temperature : -40°C ~ 85°C
- Communication
  - SQ7101 support I2C interface (max. 400Kbps)
  - SQ7103 support SPI interface (max. 5MHz@MODE 0)
- High-Security Features
  - AES-128/AES-256
  - SHA-256
  - True Random Number Generator (TRNG)
  - **Enclosure Intrusion Protection**
  - Simple/Differential Power Analysis (SPA/DPA)
  - Individual Internal Clock to Prevent Glitch Attack
  - 128-bit Unique ID
  - NIST CAVP Certification
- Support 16 keys with 128-bit or 8 keys with 256-bit
- 256 Bytes User Data
- 768 Bytes Small Zone
- 16 Monotonic Counters, Prevent replay attacks and man-in-the-middle attacks
- Low Power
  - Deep Sleep Current 250nA
- Applications
  - Accessory Authentication
  - System Anti-Clone
  - Security Smart Lock
  - Session Key Exchange
  - Chain of Trust

- Device Authentication
- Sensitive Data Protection and Encryption
- **Firmware Protection**

## Page: 2/23

iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.



Package Type

SOP8



- 8-Lead DFN (3mm x 3mm)

No. : TDDS01-S7101-EN(B)

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

		Content	
	PR	EFACE	4
	PII	N ASSIGNMENT/DESCRIPTION	5
	2.1	SQ7101 Assignment/Description	5
	2.2	SQ7103 Assignment/Description	6
	EL	ECTRICAL CHARACTERISTICS	8
1. 2.	3.1	Absolute Maximum Ratings	8
	3.2	OPERATION CONDITIONS	9
3.		Operation Conditions	9
٦.		I/O Characteristics	9
	3.3	DC CHARACTERISTICS	10
	3.2.1 3.2.2 3.2.2	Power-on Reset Characteristics	11
	3.2.Z 3.5	BROR CHARACTERISTICS	
	3.6	AC CHARACTERISTICS	13
		AC Parameters	13
	3.6.1	I2C Characteristics	14
	3.6.2	SPI Characteristics	15
	3.6.3 <b>3.7</b>	EEPROM CHARACTERISTICS	17
	APPEN	IDIX A. PACKAGE INFORMATION	18
	APPEN	DIX B. ORDERING INFORMATION	20
		DIX C. PRODUCT NUMBER INFORMATION	
4	APPEN	IDIX D. GLOSSARY	22
	REVISI	ON HISTORY	23

Page: 3/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

## Preface

1.

SQ7101/SQ7103 is high-security, low-power Secure ASIC. This device offers TRNG (True Random Number Generator), Hardware Cryptography AES-128, AES-256, SHA-256 and Anti-Tamper function. The device can support 16 keys with 128-bit or 8 keys with 256-bit.

SQ7101/SQ7103 Secure ASIC is suitable for security application, such as Accessory Authentication, System Anti-Clone, Security Smart Lock, Critical Data Encryption, and so on.

Page: 4/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

## Pin Assignment/Description

## 2.1 SQ7101 Assignment/Description

PRODUCT: SQ7101SP008C00R






Figure 2-1 Pin Assignment of SQ7101 SOP8

### PRODUCT: SQ7101N3008C00R





Figure	2-2 Pin	Assianmen	t of SQ7101	8-Lead DFN
· · · · · · ·		/		•

Pin No.	Pin Name/Pin Option	l/O Type	Function Description
1	NC	-	No Connect
2	NC	-	No Connect
3	NC	-	No Connect
4	VSS	GND	Ground
5	SDA	I/O	SDA, I2C bus data input/output
6	SCL	I	SCL, I2C bus clock input/output
7	NC	-	No Connect
8	VDD	Power	VDD Power Supply

Page: 5/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

iMO Technology Inc. No.: TDDS01-S7101-EN(B) Name : SQ7101/SQ7103 Brief Datasheet Version: V2.3 2.2 SQ7103 Assignment/Description PRODUCT: SQ7103SP008S00R CS 8 ] VDD 1 MISO [ 2 7 ] NC NC [ 3 6 ] SCLK VSS [ ] MOSI 4 5 Figure 2-3 Pin Assignment of SQ7103 SOP8 PRODUCT: SQ7103N3008S00R 8 [ ] ] CS <u>]</u>1 VDD



### Figure 2-4 Pin Assignment of SQ7103 8-Lead-DFN


Pin No.	Pin Name/Pin Option	l/O Type	Function Description
1	CS	I	SPI, Chip Select
2	MISO	0	SPI, Master In Slave Out
3	NC	-	No Connect
4	VSS	GND	Ground
5	MOSI	I	SPI, Master Out Slave In
6	SCLK	I	SPI,SPI Clock
7	NC	-	No Connect
8	VDD	Power	VDD Power Supply

Page: 6/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

The following is the recommended reference designs when using SQ7101/SQ7103 products. If the relevant pin are used, please refer to the corresponding suggestions:



Note: The 0.1 uF near the IC (VDD) in the above figure should be as close to the IC as possible

Page: 7/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

3.

No. : TDDS01-S7101-EN(B)

## **Electrical Characteristics**

## 3.1 Absolute Maximum Ratings

The absolute maximum ratings are rated values which must not be exceeded during operation, even for an instant. Any one of the ratings must not be exceeded. If any absolute maximum rating is exceeded, a device may break down or its performance may be degraded, causing it to catch fire or explode resulting in injury to the user. Thus, when designing products which include this device, ensure that no absolute maximum rating value will ever be exceeded

			(V <u>-</u>	$s_{s} = 0V$
Parameter	Symbol	Pins	Ratings	Unit
Supply Voltage	V <sub>DD</sub>		-0.3 to 6.0	V
Input Voltage	V <sub>IN</sub>	All I/O pins	-0.3 to VDD+0.3V	V
Output Current (total)	I <sub>OL</sub>	All I/O pins	50	mA
Storage Temperature	T <sub>STG</sub>		-50 to 125	°C

Page: 8/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

Name : SQ7101/SQ7103 Brief Datasheet No.: TDDS01-S7101-EN(B)

## 3.2 Operation Conditions

The following defines the electrical characteristics of the device when it is operated at voltage and temperature maximum/minimum values. Unless otherwise stated, the standard conditions were determined at "operating temperature 25 ° C and operating voltage VDD = 3.3 V".

## **Operation Conditions**

	Parameter	Symbol	Min.	Тур.	Max.	Unit
3.2	2.1 Operating Voltage	V <sub>DD</sub>	2.0	3.3	5.5	V
	Operating Temperature	Та	-40	25	85	°C

## I/O Characteristics

3.2	Parameter	Symbol	Conditions	Min.	Тур.	Max.	Unit
	Input Low Voltage	V <sub>IL</sub>		0		0.3 VDD	V
	Input High Voltage	VIH		0.7 VDD		VDD	V
	Output Low Voltage	V <sub>OL</sub>	IOL= 3 mA	0		0.1 VDD	V
	Output High Voltage	V <sub>OH</sub>	IOH= -3 mA	0.9VDD		VDD	V

# Page: 9/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

No. : TDDS01-S7101-EN(B)

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

## 3.3 DC Characteristics


Parameter	Symbol	Conditions	MIn	Тур	Мах	Unit
Operation Mode	I <sub>DD_N1</sub>	VDD=3.3V, Temp=25 °C		3		mA
Deep Sleep Mode	I <sub>DD_Ds</sub>	VDD=3.3V, Temp=25 °C		250		nA

**Page**: 10/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

Name : SQ7101/SQ7103 Brief Datasheet

## 3.4 Power-on Reset Characteristics

Ta=-40~85°C							
Symbol	Symbol Description		Тур	Мах	Unit		
tPPW	Power-on reset minimum pulse width	1	-	-	ms		
tPWUP	Warming-up time after a reset is clear and device ready	-	4	-	ms		
tVDD	Power supply rise time	0.5		5	ms		



## Figure 3-1 Operation Timing of Power-on Reset

Note : In power-down process, the VDD must be less than 0.2V, then re-power-on to ensure the IC operating normal.

Page: 11/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

## 3.5 BROR Characteristics

Ta=-40~85°C							
Parameter	Symbol	Condition	Mln	Тур	Max	Unit	
	VBROR Rising	VDD rise time and fall time > tVDD (tVDD refer to CH3.4 Power-on- Reset Characteristics)	1.95	2.0	2.05	V	
BROR detect voltage	VBROR Falling		1.85	1.90	1.95	V	

**Page**: 12/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

No. : TDDS01-S7101-EN(B)

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

## 3.6 AC Characteristics

Parameter	Symbol	MIn	Тур	Max	Unit
User Data Write Cycle Time (Note)	Twc <sub>1</sub>	6.0	-	9.0	mS
128-bit/256-bit Key Write Time (Note)	Twc <sub>2</sub>	6.0		9.0	mS

Note: Writer time is including data update.

## **AC Parameters**

	Parameter	Symbol	MIn	Тур	Max	Unit
B.6.1	Power-Up Ready Time	T <sub>PU_RDY</sub>		2800	9300	uS
St	tandby Time, Entering deep sleep mode	Т <sub>stb</sub>		55	90	uS
N	Wake-Up Ready Time, deep sleep mode	Twds_rdy		300	-	uS

Note: The Typ value is under operating temperature 25 ° C and the Sleep command changes this value.

Page: 13/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

No. : TDDS01-S7101-EN(B)

Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

## **I2C Characteristics**

Parameter	Symbol	Min	Max	Unit
Clock Frequency	f <sub>SCL</sub>	0	400	kHz
Hold Time Repeated START Condition	t <sub>hd;sta</sub>	0.6	-	us
Low Period of SCL Clock	t <sub>LOW</sub>	1.3	-	us
High Period of SCL Clock	tніgн	0.6	-	us
Setup Time for a Repeated START Condition	t <sub>su;sta</sub>	0.6	-	us
Data Hold Time	t <sub>hD;DAT</sub>	0	0.8	us
Data Setup Time	t <sub>su;dat</sub>	0.1	-	us
Rise time of both SDA and SCL	t <sub>r</sub>	20	300	ns
Fall Time of both SDA and SCL	t <sub>f</sub>	20	300	ns
Setup Time of STOP Condition	t <sub>su;sto</sub>	0.6	-	us
Bus Free Time between a STOP and START Condition	t <sub>BUF</sub>	1.3	-	us
Capacitive Load for Each Bus line	C <sub>b</sub>	-	400	pF




Figure 3-2 I2C Timing Sequence

Page: 14/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

No. : TDDS01-S7101-EN(B)


Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3

## **SPI Characteristics**

	Parameter	Symbol	MIn	Max	Unit
	SPI Frequency	f <sub>sPl</sub>		5	MHz
3.6.3	SPI Period	t <sub>spi</sub>	200		ns
	High period of the SCLK pin	t <sub>clkh</sub>	90		ns
	Low period of the SCLK pin	t <sub>clkl</sub>	90		ns
	From SPICS active to first edge	t <sub>cs_su</sub>	40		ns
	From last SCLK edge to SPICS inactive	t <sub>cs_HD</sub>	40		ns
	Time between SPI transaction	t <sub>cs_wa</sub>	1		us
	Data Input Setup Time	t <sub>si_su</sub>	10		ns
	Data Input Hold time	t <sub>si_HD</sub>	10		ns
	Data Output Valid Time	t <sub>so_vd</sub>		80	ns
	Data Output Hold Time	t <sub>so_hd</sub>	0		ns

Page: 15/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.



Name : SQ7101/SQ7103 Brief Datasheet

Version: V2.3


## 3.7 EEPROM Characteristics


Parameter	MIn	Тур	Max	Unit
Write Endurance (Sector Endurance)	100,000	-	-	Cycles
Data Retention( at 25°C)	100	-	-	Years
Data Retention( at 85°C)	20	-	-	Years


**Page**: 17/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.


## Appendix A. Package Information

SOP8









C		mm		
Symbol	Min.	Тур.	Max.	
А		-	1.75	
A1	0.10	_	0.25	
A2	1.25	-	-	
b	0.31	-	0.51	
с	0.10	-	0.25	
D		4.90 BSC		
E		6.00 BSC		
E1		3.90 BSC		
е	1.27 BSC			
L	0.40	-	1.27	
h	0.25	-	0.50	
θ	0 °	_	8 °	


**Page: 18/23** iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

No.: TDDS01-S7101-EN(B)


## Name : SQ7101/SQ7103 Brief Datasheet


Version: V2.3

## 8-Lead DFN (3mm x 3mm)









C maked		mm		
Symbol	Min.	Тур.	Max.	
А	0.70	0.75	0.80	
A1	0.00	0.02	0.05	
A3		0.203 REF.		
b	0.20	0.25	0.30	
D	2.90	3.00	3.10	
E	2.90	3.00	3.10	
е	0.50 BSC			
L	0.35	0.40	0.45	
D2	2.45	2.50	2.55	
E2	1.63	1.68	1.73	
К	0.20	-		

**Page: 19/23** iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

## Appendix B. Ordering Information

## When ordering products, please provide the following details:

Ordering Information	Product	Packaging	Provisioning Service	Description
	SQ7101SP008C00R	Т	Y	I2C, SOP8, Tape & Reel, 85°C, provisioning service
Evamolo	SQ7101N3008C00R	В	Blank	I2C, DFN 3x3, Tape & Reel, 85°C, no provisioning service
Example	SQ7103SP008S00R	В	Blank	SPI, SOP8, Tape & Reel, 85°C, no provisioning service
	SQ7103N3008S00R	Т	Y	SPI, DFN 3x3, Tape & Reel, 85°C, provisioning service

Note 1: "Packaging"- T: Tape & Reel; B: Tube/Tray

Note 2: "Provisioning service for Customers" - Y: Need provisioning service for customers; Blank: No provisioning service for customers

Page: 20/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

lo. : TDDS01-S7101-EN(B)	Name : SQ7101/SQ7103 Brief Datasheet	Version : V2.3
Appendix C. Produc	ct Number Information	
Example : MQ SQ product Product Series Sub Series Code Package Type SP SOP N3 DFN 3x3 Pin Count Code Pin		R T Y
0088Communication InterfaceCodeType.CI2CSSPIWSWI		
Designator		
Packing Code Packing T T&R B Tube		

Code	Provisioning	
Y	Yes	
Blank	No	

Page: 21/23 iMQ reserves the right to change the information in this document without prior notice. Please contact iMQ to obtain the latest version of product specification before placing your order. Use of iMQ devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMQ from any and all damages, claims, suits or expenses resulting from such use.

## Appendix D. Glossary

English	Description
AES	Advanced Encryption Standard
Ciphertext	Encrypted text
Cleartext	Text without encryption
МАС	Message Authentication Code
NONCE	Number of once
Plaintext	Text without encryption
Session Key	Key for one communication session
TRNG	True Random Number Generator

Page: 22/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.

Name : SQ7101/SQ7103 Brief Datasheet

## **Revision History**

Version	Issued Date	Description
V2.3	2025/01/09	<ol> <li>Add Packing (T) in Appendix C. Product Number Information</li> <li>Add Provisioning Service(Y) in Appendix C. Product Number Information</li> <li>Modify Appendix B. Ordering Information</li> </ol>
V2.2	2024/10/28	1. Add Appendix B. Ordering Information 2. Add Appendix C. Product Number Information
V2.1	2024/5/24	1. Sync with datasheet V2.1 full version 2. Modify "Supply Voltage" to "Operating Voltage" in 3.2.1 Operation Conditions
V2.0	2024/03/4	1. Sync with datasheet V2.0 full version
V1.9	2023/12/26	1. Sync with datasheet V1.9 full version 2. Add SQ7103 8-Lead DFN package and pin assignment 3. Add PRODUCT info : SQ7101SP008C00R, SQ7101N3008C00R, SQ7103SP008S00R, SQ7103N3008S00R
V1.7	2023/4/20	<ul> <li>1.Operating voltage change to 2.0~5.5V, modify "2.1 Absolute Maximum Ratings." And "2.2.1 Operation Conditions."</li> <li>Update "figure 2-1 Operation Timing of power-on reset" and add note.</li> <li>2. "2.6.1 AC Paramenters "add note "Power-Up Ready Time does not include the executing time for BOOTROM code. The BOOTROM code executing time is around 10ms."</li> <li>3."3.6.2 I2C Characteristics " update the figure of t<sub>HD;DAT</sub> Add SDA and SCL to "figure 2-2 I2C Timing Sequence."</li> </ul>
V1.6	2023/3/30	1.Modify "CH Power-on Reset Characteristics"
V1.5	2022/7/21	1.Modify the description of small zone 2.Add package type "8L DFN 3x3 " to "1.1 pin assignment/description" and "Appendix A
V1.4	2021/12/29	1.Modify "2.4 Power-on Reset Characteristics" 2. Add "CH2.5. BROR Characteristics"
V1.3	2021/6/24	<ol> <li>Solve DecRead issue that Param2 of command is not matched with</li> <li>FirstBlock.Param2.</li> <li>Add : "4.2 SQ7103 Pin Assignment/ Description</li> <li>Add : "5.4.3 SPI Characteristics"</li> <li>Add "CH5.5 EEPROM Characteristics" description.</li> <li>Add "CH 7.1 Command Introduction" description.</li> <li>Add "CH 7.3.13 INFO Command "selector for CountStatus.</li> <li>Renew "CH7.3.25 SHA Input Parameters" Mode</li> <li>Add "Appendix A. Package Information"</li> </ol>

Page: 23/23 iMO reserves the right to change the information in this document without prior notice. Please contact iMO to obtain the latest version of product specification before placing your order. Use of iMO devices in life support is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless iMO from any and all damages, claims, suits or expenses resulting from such use.